

<b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>				1. CONTRACT ID CODE	PAGE 1 OF 3 PAGES
2. AMENDMENT/MODIFICATION NO. AMENDMENT NO. 0003		3. EFFECTIVE DATE 08/06/12	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable) 12-0006	
6. ISSUED BY CODE sgj  Officer in Charge of Construction MCI-East 1005 Michael Road Camp Lejeune, NC 28547-2521		7. ADMINISTERED BY (If other than Item 6) CODE  See Item 6			
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)				(X)	9A. AMENDMENT OF SOLICITATION NO. N40085-12-R-0006
				X	9B. DATED (SEE ITEM 11) 07/23/12
CODE					10A. MODIFICATION OF CONTRACT/ORDER NO.
					10B. DATED (SEE ITEM 11)
FACILITY CODE					

**11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS**

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers  is extended,  is not extended.  
 Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:  
 (a) By completing items 8 and 15, and returning \_\_\_\_\_ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted;  
 or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS.  
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor  is not,  is required to sign this document and return \_\_\_\_\_ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

Project 12-0006, Renovate Bathrooms, HP-55

~SEE CONTINUATION PAGE~

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR  (Signature of person authorized to sign)		16B. UNITED STATES OF AMERICA  (Signature of Contracting Officer)	
15C. DATE SIGNED		16C. DATE SIGNED	

1. Question: Per elevation views on drawing A-402, new doors and frames in Offices - Toilet Rooms are to be painted. There is no mention of doors and frames to be painted in sleeping rooms on elevation view on drawing A-401. Are sleeping room doors and frames to be painted?

Answer: Please refer to General Construction Note 2, found on sheets A-101, A-102, A-103, and A-402. "Paint all bathroom doors and frames."

2. Question: In the sleeping rooms and office toilet rooms, it tells us to "remove existing gypsum wall board ceiling - entire room, +/- 7'6" AFF and light fixture." It does not tell us to remove existing ceiling framing. When demolishing gypsum ceilings, typically the existing framing will be damaged and cannot be re-used. Is the intent to replace gypsum board ceiling and framing?

Answer: See General Note #2 sheets A-101, A-102, and A-103. Contractor shall exercise care when demolishing existing ceiling to preserve existing framing; however, if at the contractors discretion it is more cost advantageous to provide new framing, then that is acceptable.

3. Question: Per detail 1 on drawing A-402, there is no mention of demolishing existing vanity and countertop. Per detail 2 on drawing A-402, there is no mention of installing new vanity or countertop. Per detail 4 on drawing A-402, it tells us to "provide new solid surface countertop w/ integral 4" backsplash and drop-in sink. Provide new vanity cabinet with three equal drawers and doors." Which detail is right? Are we providing new and demolishing old?

Answer: Refer to Elevation 4/A-402. Provide new vanity cabinet, as drawn, and solid surface countertop with integral 4" backsplash. Provide an integral bowl in lieu of a drop-in sink.

4. Question: There is no mention of demolishing and installing new shower drains. Are we to demolish old shower drains and install new shower drains?

Answer: Shower drains are to be replaced. Refer to detail 1/A-401 and Specification Section 22 00 00.

5. Question: Drawing M-101 tells us to "Remove existing exhaust fan and clean housing and intake grille for reuse. Repair or replace damaged fans including intake grilles." This is very open ended. How many exhaust grilles are we to assume or already not working? Please quantify the number of exhaust fans we are to assume are not currently working for bidding purposes.

Answer: Provide new exhaust fans/grilles in lieu of cleaning and reinstalling the existing.

6. Question: Per plumbing fixture schedule, W1 water closet model specified is a floor mounted, floor outlet water closet. Specification section 22 00 00, paragraph 2.4.1, tells us to provide floor mounted, floor outlet water closet. After site visit, existing water closets are floor mounted, back outlet water closets. Are we to provide floor mounted, floor outlet water closets which would require wall and floor cutting and patching to rerun the sewer piping? If so, what is the material type of the existing sewer system? Or are we to provide floor mounted, back outlet water closets?

Answer: Provide back outlet floor-mounted water closets to avoid unnecessary piping changes.

7. Question: A-101, 102, 103 construction note 2, 5, and 9 states to provide backerboard. A-401 detail 6 shows backerboard inside shower, but shows glass mat gypsum board outside the shower. Which product should be used for walls outside the showers?

Answer: Provide 5/8" glass mat gypsum board on new work outside of the showers.

8. Question: A-401 detail 5 states 5/8" cementitious backerboard. A-401 detail 6 states 1/2" cementitious backerboard. Which dimension is required?

Answer: Provide 5/8" cementitious backer board in all shower wall locations.

9. Question: The new work notes on the plumbing drawings are very specific about the work to be done. The plumbing specifications on sheet P-0001 make reference to work that is not shown on the new work drawings. For example, note 10 requires new water hammer arrestors for all plumbing and kitchen fixtures. What about walls we are not disturbing? Where are the kitchen fixtures?

Answer: On Sheet P-001, Note 10 – **DELETE** the reference to kitchen equipment. **DELETE** Note 18 from Sheet P-001.

10. Question: Note 8 mentions insulation of all the piping systems. How about the piping that is in walls not scheduled for demo?

Answer: Referencing Sheet P-001, Note 8 – provide insulation for new plumbing piping only.

11. Question: The architectural drawings require demolition of the existing floor drains. The plumbing drawings show replacement of shower heads and valves but do not show the floor drains.

There are several instances where the new work notes are not consistent with the scope of work described in the drawings. Please clarify the intended scope of work.

Answer: New tile is to be provided in the showers with new valve and drains, specified on the Plumbing Fixture Schedule on Sheet P-601. Provide new shower drains, as specified in Specification Section 22 00 00.

12. The Contractor may work in no more than six sleeping rooms at one time.